



NOTES:

- ① RAILING: SCHEDULE 40 4in O.D. (100mm), 4in x 6in REDUCER (100mm x 150mm), SCHEDULE 40 6in O.D. (150mm) w/PIPE FLANGE POWDER COATED - "SAFETY YELLOW".
- ② RECEPTACLE: SCHEDULE 40 6in I.D. (150mm) w/PIPE FLANGE POWDER COATED - "SAFETY YELLOW". PRIMER COATED REBAR OR SLIP STOP WELDED TO SIDE.
- ③ SIGN MOUNTING TABS: 3/4in x 2in x 1in with 3/8 HOLE (6.3mm x 50mm x 25mm with 9.4mm HOLE). SIGN: 3/4in. (19mm) PLYWOOD BACKED, ALUMINUM, REFLECTIVE SIGNS ON EACH BARRIER. RMOW TO PROVIDE WORDING AS REQUIRED.
- ④ INSTALL 42in (1050mm) TO ASPHALT SURFACE.
- ⑤ INSTALLATION OF PRECAST CONCRETE RECEPTACLE TO BE ON COMPACTED BASE WITH COMPACTED BACKFILL.
- ⑥ GATE FLANGE & RECEPTACLE FLANGE TO MATCH.
- ⑦ WELD 3/4in ROD COUPLER (ON TANGENT) FOR MARKER PLACEMENT.
- ⑧ WELD 3in x 1 1/2in x 1/4in BARSTOCK with 45° CHAMFERED EDGES 20in c/c ON TOP OF RAILING.
- ⑨ WELD 6in x 4in x 4in PROTECTIVE SHROUD TO RECEPTACLE FLANGE TO COVER LOCKING FEATURES.



RESORT MUNICIPALITY of WHISTLER

UTILITIES ACCESS GATE

DRAWN BY: BL

DATE: AUGUST 2008

SCALE: N.T.S.

DWG. NO.: R8-A