

March 25, 2019

A – Addendum #3

RFP – Water Main Leak Detection Services - RFP # E21007-2019

The following clarifications are to be made to the RFP as a result of clarification requests and questions received from a Proponent in regards to the intent and scope of the RFP.

Q) What is the expected time frame of the work?

A) *Ideally, the scope of work presented in the RFP would be completed within 1 year with commencement as soon as is reasonably possible. However, there may be constraints or delays due to operational restrictions or due to the criticality of some of the water mains (ie. they may have to be scheduled for inspection either immediately or in the fall). The RMOW will work with the successful proponent to develop a schedule that meets the needs of the operations.*

Q) What is the approximate pressure of the Alta Vista network?

A) *The Alta Vista zone distribution network pressure range is ~ 77 to 115 psi.*

Q) Can flow characteristics (direction, pressure, flow velocity, etc.) be made available for P280 to Crabapple Drive and the Alta Lake Crossing?

A) *P280 to Crabapple Drive:*

- *Flow range ~ 2 to 7 m³/min*
- *Pressure is ~ 180-200 psi*

Alta Lake Crossing:

- *The Alta Lake Crossing data is more complicated to extract and cannot be provided at this time.*

More information is available but will take time to extract.

End of Addendum

