
Addendum 1

ISSUE DATE: September 28, 2023

CLIENT NAME: Resort Municipality of Whistler

FROM: Chelsey Roberts, AScT, Resort Municipality of Whistler

RE: **South Whistler Water Upgrade
Contract E20307**

In accordance with the provision contained in the "Instructions to Tenderers" for Contract No. E20307, Addendum No. 1 is hereby issued.

The following changes, additions, and/or deletions are hereby made a part of the Contract Documents for the above noted Contract, Invitation for Tender as fully and completely as if the same were fully set forth therein:

Revise the following to Form of Tenders

FT 2.2 to achieve Substantial Performance of the Work on or before **May 30, 2025**.

Replace

Form of Tender Appendix 2 with the attached.

Replace

Table 01 14 16-A and Table 01 14 16-B with the attached

South Whistler Water Improvements Phase II

(TITLE OF CONTRACT)

See paragraph 5.3.2 of the Instructions to Tenderers – Part II.

Indicate Schedule with bar chart with major item descriptions and time.

MILESTONE DATES: Substantial performance by May 30, 2025

ACTIVITY	CONSTRUCTION SCHEDULE									
	1	2	3	4	5	6	7	8	9	10
Mobilization to Site										
Demolition										
Concrete and Masonry										
Metals										
Rough Carpentry										
Thermal and Moisture Protection										
Openings and Finishes										
Specialties										
Equipment										
Process Interconnections and Controls										
Process Gas and Liquid Handling										
Plumbing systems										
Electrical Systems										
Civil, including buried tanks, piping and earthworks										
HVAC systems										
Water and Wastewater Equipment										
Restoration										
Demobilization										

Table 01 14 16-A Schedule of Tie-Ins					
Tie-In No.	Stage	Existing (Connecting) Line Size & Service	Tie-In Building/Location	Construction Stage	Remarks
1	Stage 2.1	N/A	Inside W212	Concurrent with P291 Construction	Preparation work for Stage 2.2
2	Stage 2.2	400mm PC350 TR Flex 400mm PC350 Restrained	Interpretive Forest Parking Lot	Post P291 Construction	
3	Stage 2.3A	250mm PC350 DI (Restrained) 350 PC350 DI (Restrained)	Interpretive Forest Parking Lot	Post P291 Construction	350mm/250mm reducer required on new tee
4	Stage 2.3B	75mm Steel 150mm Steel	Inside W212	Post P291 Construction	Sequenced installation of new piping to existing Function Junction PRV
5	Stage 2.4	300/400mm PC350 DI Unrestrained	Gravel lot at end of Lyman Road	Post P291 Construction	Existing w/m is 300mm along highway and 400mm to Interpretive Parking Lot
6	Stage 2.5	250mm PC350 DI Restrained to 300mm PC350 DI unrestrained	Gravel lot at end of Lyman Road	Post P291 Construction	Existing w/m is 300mm to termination and 250mm across highway

Table 01 14 16-B Schedule of Shutdowns					
Shut-down No.	Equipment and Service Lines Out-of-Service During Shutdown	Equipment In Operation During Shutdown	Tie-In Nos.	Maximum Duration	Calendar Period
A	PRV284 Supply to Cheakamus Distribution System (Stage 2.2)	No supply from Gondola Reservoir to Cheakamus Water System	1	8hrs	N/A
B	Cheakamus Reservoir (Stage 2.3A)	No supply from Cheakamus Reservoir to Cheakamus Water System (supply via Gondola and new PRV)	1	8hrs	N/A
C	W212 to Gondola Reservoir (Stage 2.4 and Stage 2.5)	No supply from W212 to Gondola or Whistler Water System	1	14 days	March-April 2025